



May 4, 2005

QUOTE #05009-Rev A

Fred Jones
 GSI
 3826 Arch Avenue
 Grand Island, NE 68803
 Phone: 308-381-1987
 Fax: 308-381-2467

**DIVERSIFIED
 REMEDIATION**
and
CONTROLS
 INCORPORATED

RE: GSI Job #035881 Former Wikard Station, Lexington, NE

Dear Fred,

Thank you for the opportunity to provide the following proposal. Please let us know if you have any questions or need any additional information. We look forward to working with you on this project.

Section A. SVE System

- | | | |
|----------------|---|--------------------|
| Item 1A | 1 SVE blower package
High Pressure Radial Blade Blower (Cincinnati)- 800 cfm @ 38"wc
10 hp, 3-phase, 230/460v, XP motor
Package includes the following: <ul style="list-style-type: none"> > Vacuum indicators > Discharge silencer (6") > Temperature gauge > Sample valve > Miscellaneous plumbing | \$ 5,675.00 |
| Item 2A | 1 Air/water separator package
Rotron Model MS1000 (at 800 cfm the ΔP is approximately 3.5" wc)
Package includes the following: <ul style="list-style-type: none"> > Vacuum relief valve > Site tube > High-level switch > Drain ball valve > Miscellaneous plumbing | \$ 2,501.00 |
| Item 3A | 1 SVE manifold package
The main line includes the following: <ul style="list-style-type: none"> > Dilution valve with filter/silencer (plumbed to the outside of trailer) > Temperature gauge. Each individual line includes the following (6 lines) <ul style="list-style-type: none"> > Throttling valve BRASS GATE VALVE > One foot of clear PVC > Vacuum indicator and sample valve > Miscellaneous plumbing | \$ 1,845.00 |

Jo 5-6-05

Section B. Control System

- | | | |
|----------------|---|--------------------|
| Item 1B | 1 DRC U.L. listed system controller-PLC logic (Nema 4)
Each motor circuit to include: H/O/A switch, Green run light, Motor Starter w/overload protection, IEC motor contactor, hour meter and cycle timer. Red fault indicator light for each latch circuit.

DRC proposes a control panel to include controls for the following: <ul style="list-style-type: none"> ➤ SVE blower circuit ➤ SVE air/water separator tank high-level latch circuit Other items included: <ul style="list-style-type: none"> ➤ Programmable logic controller (PLC) ➤ Panel heater | \$ 3,805.00 |
|----------------|---|--------------------|

Section C. Trailer Mounted Equipment

- | | | |
|----------------|--|---------------------|
| Item 1C | 1 SVE trailer package
Enclosed pre-fabricated insulated trailer (8.5' wide x 12' long)
DRC panel mounted on the outside of the trailer
Explosion proof wiring (Class 1, Div. 2) of all equipment to the DRC control panel
Includes mounting & plumbing of the following: <ul style="list-style-type: none"> ➤ SVE System ➤ Explosion proof heater with thermostat ➤ Explosion proof exhaust fan with thermostat ➤ Exhaust louvers ➤ Explosion proof lights and light switch ➤ Control panel ➤ Service panel Trailer options include: <ul style="list-style-type: none"> ➤ Insulated walls, ceiling and floor ➤ Double rear doors ➤ Interior height of 7' 6" ➤ Two stabilizer jacks | \$ 12,240.00 |
|----------------|--|---------------------|

Total (excluding startup & shipping): \$ 26,066.00